BRUHATH BANGALORE MAHANAGARA PALIKE,

Office of the Executive Engineer Dasarahalli Division,

Schedule-B

NAME OF WORK: Construction of concrete roads and other works at Abbigere Colony from 1st to 6th cross in ward no 12, Shettyhalli sub Division

Sl. No	Description of work	Unit	Qty	Sanctioned rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Dismantling of cement concrete pavement by Cummechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	127.21	807.72	Rupees Eight hundred seven and Paise seventy two only
2	Removing B.S. slab of Drain and stacking etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Sqm	453.75	104.94	Rupees One hundred four and Paise ninety four only
3	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2018-19, Page No.142, Item No. 19.1) including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 5 kms distance by using private vehicle this includes the cost of loading and unloading charges complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	856.39	211.79	Rupees Two hundred eleven and Paise seventy nine only
4	Plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scafofolding and centering etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	125.82	5421.90	Rupees Five thousand four hundred twenty one and Paise ninenty only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

5	Providing laying palin / reinforced cement concrete for side Drain using M20 nominal mix concrete with OPC at 300 kgs with 20 mm and down size granite metal coarse aggregates at 0.69 cum fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., completet excluding cost of steel ae per MMORTH specification No 1500, 1700, 2200. including cost of materials, labour, HOM etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	179.45	7070.20	Rupees Seven thousand seventy and Paise twenty only
6	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Tonne	6.70	75223.36	Rupees Seventy five thousand two hundred twenty three and Paise thirty six only
7	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides complete as per specifications and as per the direction of Engineer-in-charge of the work.	Sqm	769.50	1651.00	Rupees Two thousand three hundred thirty seven only
8	Removing and resetting of foot path slab etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Sqm	1109.25	208.82	Rupees Two hundred eight and Paise eighty two only

EXECUTIVE ENGINEER-4
Signature of Contractor
KRIDL, BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER
Executive Engineer
Dasarahalli Division
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.